

Project No.:		P24136															
Project Name:		Mastercard Two South County															
Date:		14/01/2026															
File Name:		Fire Alarm Cause and Effect															
Status:		For Contract															
Revision:		2															
		CAUSE	EXTERNAL CARPARK				LANDLORD / TENANT AREAS										
			Single Smoke Detector	Single Heat Detector	Two Detectors	Break Glass Unit	Single Heat Detector - All Areas	Single Smoke Detector - All Areas	Two Detectors or one Break Glass Unit + 1 Detector - All Areas	Break Glass Unit - All Areas	Multiple Detectors / Break Glass Units in All Areas	BCU in Stairs 1,2, & 3	BCU in Atrium Ground Floor	Single Detector or AOV control switch in Atrium - Ground Floor	Single Detector or AOV control switch in Staircore - 1,2, or 3	VESDA System in Atrium	VESDA System
			A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
EFFECT																	
1	Displayed on main panel	ALERTS	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•
2	System on 3 minute Alert at Panel and notify resident building manager. System goes into full alarm after 3 minute timeout		•	○	○	○	•	•	○	○	○	○	○	○	○	○	○
3	Open AOVs/auto windows in affected staircore immediately	AOV	○	○	○	○	○	○	○	○	○	•	○	○	•	○	○
4	Open AOV in Atrium at High & Low Level		○	○	○	○	○	○	○	○	○	•	•	○	•	○	○
5	Send signal to FSD interface		○	○	•	•	○	○	•	•	•	•	○	○	•	•	•
6	Lifts to return to ground floor level and landing doors to open and remain open (except where detector activation is in the ground floor lift lobby in which case the lift is to return to first floor level, doors open to allow passengers to exit and remain open)	LIFTS	○	•	•	•	○	○	•	•	•	•	○	○	•	•	•
7	External Sounder/Strobe activated	ALERTS	○	•	•	•	○	○	•	•	•	○	○	○	•	•	•
8	Sounders full evac all floors including roof plant areas		○	•	•	•	○	○	•	•	•	○	○	○	•	•	•
9	Auto Dial Remote Monitoring Station on full evacuation		○	•	•	•	○	○	•	•	•	○	○	○	•	•	•
10	Send signal to MCC Panels to shut down	MECH PLANT	○	•	•	•	○	○	•	•	•	○	○	○	•	•	•
11	New Roof MCC Power Panel to Shutdown		○	•	•	•	○	○	•	•	•	○	○	○	•	•	•
12	HVAC system to shut down		○	•	•	•	○	○	•	•	•	○	○	○	•	•	•
13	BMS Outstations to receive signal to shutdown		○	•	•	•	○	○	•	•	•	○	○	○	•	•	•
12	All door held open on emergency catches to release and close	ACCESS CONTROL	○	•	•	•	○	○	•	•	•	○	○	○	•	•	•
13	Access control system doors fails safe - Doors locking mechanism dis-engages		○	•	•	•	○	○	•	•	•	○	○	○	•	•	•
14	Open security pass gates at reception		○	•	•	•	○	○	•	•	•	○	○	○	•	•	•
15	Barriers to car park entrance to power open and remain open		○	•	•	•	○	○	•	•	•	○	○	○	•	•	•

Notes		
1	○	in each instance denotes effect INACTIVE
2	●	in each instance denotes effect ACTIVE
3		Full evac to be available via press button at front of main FAP or FARP
4		Any alert not cleared within the time limit will result in an evacuate signal
5		**Alarm investigation time TBA with design team
6		***On activation of local device only
7		Crossflow shaft to open on subject floor / lobby only.
8		Mechanical ventilation to shut down on activation of FDAS.
9		Passenger Lifts Descend to 1st Floor on receipt on receipt of fire signal from ground lobby
10		Double Knock Shall mean; 2 No. Devices
11		Fire Alarm Network Controls: All Panels to Silence/Reset